

PIPE JACKING AT CORWEN FLOOD PREVENTION SCHEME, CORWEN, DENBIGHSHIRE

Client:

**Denbighshire County
Council**

Summary:

Installation of an inverted syphon
under main road as part of a large
flood alleviation scheme.



Iseki cutter head ready for action



View along the tunnel

PROJECT DETAILS

PIPE JACKING

- New sewer for flood alleviation
- DN5000 x 9m caisson drive shaft
- DN4000 x 9m deep caisson reception shaft
- 106m x DN1500 pipe jacking using Iseki Unclemole

GROUND CONDITIONS

- Wet Sand and Gravel