

## D558 PALM PAPER, KINGS LYNN

Programme:

**January 2019**

Clients:

**Brookes & Wood**

Summary:

**Install three electric ducts**



### PROJECT DETAILS

A E Yates Trenchless Solutions Ltd were contracted to install three separate 180mm electric ducts at 60m each under a service road within a factory complex. The accuracy was essential to avoid drains, electric ducts and lots of closely installed services throughout the bores.

As you can see in one picture above, the drill head is just below an electric duct that the client had exposed. We couldn't install this in a trefoil as we usually do due to the small working room hence the three separate ducts.

This to A E Yates Trenchless Solutions Limited is what our drillers excel in. Well done to the drilling team on the contract.

**Ground Conditions:** Clay