

## HORIZONTAL DIRECTIONAL DRILLING AT KEADBY WIND FARM

Client:

**Balfour Beatty Regional  
Civil Engineering**

Summary:

Installation of 34 Wind Turbine  
generators.



### PROJECT DETAILS

Supply and install 3No 120m long HDD crossing (355, 560 and 630mm pipe) under drainage ditches. Along with the 3No crossings AEYTS were also contracted to install sub ducting within the crossings.

All pipe was welded on site before installation and haul roads were installed to gain access to the drill locations. This contract was programmed for 7 weeks but was completed in 4 weeks, to the satisfaction of the client.

#### GROUND CONDITIONS

- Sandy Clay

