



## HORIZONTAL DIRECTIONAL DRILLING AT SALTFLEETBY, NORTH LINCOLNSHIRE

Client:

**BBUSL @  
One Alliance**

Summary:

Watermain replacement for  
Anglian Water



### PROJECT DETAILS

We have just completed the first installation on a water main replacement scheme for Anglian Water at Saltfleetby, North Lincolnshire. The full scheme involves a number of drainage ditch/culvert crossings to install a 280mm OD SDR11 main. Most of the drills have been planned at 60m lengths, but the first section included an additional section of carriageway to avoid opencut work in front of a private access which increased the drill length to a total of 120m.

Ground conditions for the drills are favourable to the method consisting of soft-firm silty clay. With the first drill taking only 12hrs to complete from initial set-up to de-mob, we hope the remaining installations go as smoothly.