



RNLI BERTH RETAINING WALL, HARTLEPOOL

Client:
RNLI (Trading) Ltd

Summary:
We were asked to construct a permanent retaining wall for the RNLI at Hartlepool



Working using the Movax

PROJECT DETAILS

The project involved the installation of permanent sheet piles for the new retaining wall for the RNLI Lifeboat Station at Hartlepool Docks

We used AU20 sheet piles at 10m, interlocked to form a 29.2m permanent retaining wall. We used our E385 tonne Excavator with the Movax SPH75 attachment

The works took 3 weeks to complete with a contract value of £84K



AU16 Sheet Pile Permanent Retaining Wall



Tidal Working at Hartlepool for the RNLI



The Pile line at Finished Level